

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20267-00-01  
Spot: SWNENWSW Sec/Twnshp/Rge: 7-33S-40W  
2036 feet from S Section Line, 4517 feet from E Section Line  
Lease Name: SANTA FE TRAIL A Well #: 3-5  
County: MORTON Total Vertical Depth: 5980 feet

Operator License No.: 34408  
Op Name: CISCO OPERATING LLC  
Address: 6900 N. DALLAS PKWY, STE 740  
PLANO, TX 75024

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5525		
CIBP		5660		
CIBP		5750		
CIBP		5890		
PROD	4.5	5960	0	WITH 250 SX CMT
SURF	8.625	1616		WITH 800 SX CMT

Well Type: EOR UIC Docket No: E23598.1 Date/Time to Plug: 01/07/2013 10:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: GILBERTO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Run tbg & tag existing Cement Retainer @5300', circulate hole w/ mud & cap w/ 5 sks cement. Pull up hole w/tbg @ 4570', mix & spot 15 sks Class "C" cement to cover Sq'd Csg leak @ 4549', POH w/ tbg, load & test csg @ 500 psi. Perf squeeze holes @ 1666', RU down 4 1/2" casing & squeeze 8 5/8" shoe w/ 80 sks Class "C" cement & displace balanced plug to 1350'. WOC. Tag TOC & perf squeeze holes @ 700', RU down 4 1/2" casing & circulate to surface w/ 190 sks cement.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/08/2013 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CMT RETAINER @ 5300' WITH 5 SX CMT. PUMP 15 SX CMT @ 4570' OVER SQUEEZE PERFS @ 4549'. PERFORATE @ 1650' & SQUEEZE WITH 80 SX CMT. PERFORATE @ 700' & CIRCULATE CMT TO SURFACE WITH 195 SX CMT LEAVING 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
5912	5918		
5848	5868		
5700	5706		
5618	5623		
5373	5377		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

RECEIVED  
JAN 18 2013

KCC WICHITA

District: 01

RECEIVED

JAN 15 2013

KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)  
cc to WCC 1/15/13

*AMY*