

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20354-00-00  
Spot: SWNW Sec/Twnshp/Rge: 7-33S-40W  
3343 feet from S Section Line, 4538 feet from E Section Line  
Lease Name: SANTA FE TR Well #: A-3-7  
County: MORTON Total Vertical Depth: 5670 feet

Operator License No.: 34408  
Op Name: CISCO OPERATING LLC  
Address: 6900 N. DALLAS PKWY, STE 740  
PLANO, TX 75024

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5540		
DVT		3035		WITH 500 SX CMT
PROD	4.5	5670	0	WITH 750 SX CMT
SURF	8.625	1612		WITH 800 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/04/2013 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: GILBERTO Company: ORR ENTERPRISES, INC. Phone: (580) 251-8618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/07/2012 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CMT RETAINER @ 5370' WITH 10 SX CMT. PLUG AT 3085' WITH 15 SX CMT. FULL CIRCULATION. TOOH W/TBG. RUN BOND LOG. TOC @ 600'. PERFORATE @ 570'. TIH W/TBG TO 1656' & SPOT 20 SX CMT. PULL TBG TO 570'. ATTEMPT TO PUMP INTO PERFORATION @ 570' @ 1000#. COULD NOT. RUN TBG TO 650' & CIRCULATE 1/2" CASING FULL OF CMT WITH 40 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS & PRESSURE TO 300#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
5574	5596		
5393	5402		

RECEIVED  
JAN 11 2013  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

*[Signature]*  
1/9/13

(TECHNICIAN)

RECEIVED

JAN - 8 2013

KCC DODGE CITY