

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23229-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 18-32S-5E  
2313 feet from S Section Line, 4884 feet from E Section Line  
Lease Name: BARNETT Well #: 3  
County: COWLEY Total Vertical Depth: 2450 feet

Operator License No.: 33277  
Op Name: COOPER, ALBERT L.  
Address: PO BOX 381  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1500		
PROD	4.5	2515	300	75 SX
SURF	8.625	150		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/28/2012 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.  
Proposal Revd. from: ALBERT COOPER Company: COOPER SERVICE CO. Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/18/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

11-28-2012, RIH ON WIRELINE SET PLUG @ 2345', SANDED BACK ON TOP OF PLUG @ 2300'. DUMP BAILED 4 SXS CEMENT ON TOP. RIH ON WIRELINE SET PLUG @ 1400', SANDED BACK @ 1350', DUMP BAILED 4 SXS CEMENT ON TOP. CUT CASING @ 300', LAYED DOWN 15 JOINTS 4-1/2" CASING. RIH W/TBG @ 255', COPELAND ACID SERVICE ESTABLISHED CIRCULATION AND MIXED & PUMPED 85 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 12-18-2012. COPELAND ACID CEMENT TICKET #14750.

Perfs:

Top	Bot	Thru	Comments
2350	2352		CSG
1464	1465		CSG PEACOCK


RECEIVED  
JAN 08 2013  
KCC WICHITA

Remarks: COMPLIANCE / 10 YR RULE / DENIED TA

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)