

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-26249-00-00  
Spot: SENWNESE Sec/Twnshp/Rge: 34-11S-19W  
2260 feet from S Section Line, 720 feet from E Section Line  
Lease Name: JENSEN TRUST Well #: 34-9-11-19  
County: ELLIS Total Vertical Depth: 3795 feet

Operator License No.: 34546  
Op Name: KLABZUBA OIL & GAS, INC.  
Address: 700 17TH ST, STE 1300  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3753		155 SX
SURF	8.625	263		124 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/18/2013 10:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DEAN WALLACE Company: KLABZUBA OIL & GAS Phone: (316) 841-4461

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.  
DV Tool at 2032' w/420 sx cement.  
Perforations: ARB/3668' - 3676'.  
Took pump in rate on 1/16/2013.  
GPS: 39.05121 -099.41052

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/18/2013 12:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Rigged to 5 1/2" casing and mixed and pumped 75 sx cement with 300 # hulls mixed in followed by 11 sx gel, followed by 180 sx 60/40 pozmix with 200 # hulls mixed in. Pumped 5 1/2" casing to pressure with 600 psi and 275 psi shut in pressure.  
Rigged to 8 5/8" casing and pumped 10 sx cement to pressure with 200 psi and 200 psi shut in pressure.

Perfs:

Top	Bot	Thru	Comments
3668	3676		


RECEIVED  
JAN 24 2013  
KCC WICHITA

Remarks: CONSOLIDATED OILWELL SERVICES LLC TICKET # 39280

Plugged through: CSG

District: 04

Signed

  
2/08/13

(TECHNICIAN)

CM

JAN 20 2013