

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20662-00-00  
Spot: NW Sec/Twnshp/Rge: 21-20S-40W  
3910 feet from S Section Line, 4028 feet from E Section Line  
Lease Name: KING L Well #: 2  
County: GREELEY Total Vertical Depth: 2830 feet

Operator License No.: 4894  
Op Name: HORSESHOE OPERATING, INC.  
Address: 110 W LOUISIANA STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2828	0	WITH 485 SX CMT
SURF	8.625	242		WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/17/2012 9:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LARRY SPARGER Company: HORSESHOE OPERATING Phone: (620) 384-9638

Proposed  
Plugging  
Method:

PLUG 4-1/2" W/250# HULLS & 185 SX 60/40 POZ 4% GEL. PLUG ANNULUS W/100 SX 60/40 POZ 4% GEL.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/17/2012 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CEMENT FROM 2803' TO 0' USING 250# HULLS & 210 SX CMT. PRESSURE TO 500#. HOLDING. PUMP 15 SX CMT DOWN ANNULUS & PRESSURE TO 500#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2793	2803		
2786	2789		


RECEIVED  
JAN 11 2013  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

DEC 27 2012

KCC DODGE CITY