

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22527-00-00  
Spot: SESENE Sec/Twnshp/Rge: 23-18S-26W  
995 feet from N Section Line, 295 feet from E Section Line  
Lease Name: WATSON Well #: 1  
County: NESS Total Vertical Depth: 4414 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3980		WITH 2 SX CMT
PROD	5.5	4411	0	WITH 125 SX CMT
SURF	8.625	257		WITH 165 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/22/2013 10:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/22/2013 4:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN CIBP TO 3980' WITH 2 SX CMT. FOUND A 4 1/2" LINER HAD BEEN RUN. RAN A BOND LOG 2000' TO SURFACE. FOUND CMT TO 300'. RUN TBG TO 1984' & CIRCULATED WITH 130 SX CMT. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE OF 5 1/2" & 8 5/8" & PUMPED 35 SX CMT. PRESSURED TO 500# & HELD. TIED ONTO BACKSIDE OF 4 1/2" CASING & COULDN'T PUMP IN TO.

Perfs:

Top	Bot	Thru	Comments
4411	4414		
4111	4414		open hole

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier (TECHNICIAN)  
1/23/13

RECEIVED  
JAN 23 2013  
KCC DODGE CITY

RECEIVED  
JAN 31 2013  
KCC WICHITA

*DMJ*