

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20906-00-00  
Spot: E2W2SESE Sec/Twnshp/Rge: 35-31S-35W  
680 feet from S Section Line, 805 feet from E Section Line  
Lease Name: RAY BARTON Well #: 2  
County: STEVENS Total Vertical Depth: 6261 feet

Operator License No.: 33127  
Op Name: CHAPARRAL ENERGY, L.L.C.  
Address: 701 CEDAR LK BLVD  
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6013		WITH 2 SX CMT
DVT		3200		
PROD	5.5	6258	0	WITH 241 SX CMT
SURF	8.625	1835		WITH 670 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/14/2013 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: GILBERTO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 6013' WITH 5 SX CMT. PLUG AT 3250' WITH 20 SX CMT. LOAD & TEST CASING TO 500 PSI. PERFORATE. PLUG AT 1865' WITH 80 SX CMT. PERFORATE. PLUG AT 700' WITH 185 SX CMT. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 01/15/2013 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 6013' WITH 2 SX CMT. PUMP 20 SX CMT AT 3250' ACROSS DV TOOL @ 3200'. PERFORATE AT 1865'. TAKE INJECTION RATE. SPOT 80 SX CMT BALANCED PLUG THROUGH PERFS LEAVING 30 SX CMT INSIDE THE 5 1/2" CASING. FULL CIRCULATION. PERFORATE @ 700 & CIRCULATE CMT TO SURFACE WITH 190 SX CMT LEAVING CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
6053	6064		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED

JAN 22 2013

KCC DODGE CITY

RECEIVED  
JAN 31 2013  
KCC WICHITA

RND