

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-069-20420-00-00  
Spot: SESWSESE Sec/Twnshp/Rge: 9-24S-30W  
182 feet from S Section Line, 675 feet from E Section Line  
Lease Name: O'BRATE GATES Well #: 1-9  
County: GRAY Total Vertical Depth: 4869 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	283		WITH 180 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/14/2012 12:30 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: EMIDIGO ROJAS Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1980' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 540' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 12/14/2012 2:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

1ST PLUG AT 1980' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 540' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.


Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed



(TECHNICIAN)

RECEIVED

DEC 18 2012

KCC DODGE CITY

RECEIVED  
DEC 26 2012  
KCC WICHITA

BNY