

1050293

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-20,442 0000

NW SE SW, SEC. 5; T 16 S, R 16 W/EK
990 FSL feet from N SE Corner of
3630 FEL feet from W SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Shade Well # 2

Operator: Rains & Williamson Oil Co., Inc.
Name & Address 435 Page Court Building
220 West Douglas
Wichita, KS 67202

County Rush
Well Total Depth 3496 113.62 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1024

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 23 Month: July Year: 1984

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" set at 3496'

1st plug sand back to 3450' and dump 5 sx cement on top of sand through bailer

2nd plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 120 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 23 Month: July Year: 1984

ACTUAL PLUGGING REPORT 5 1/2" set at 3496'

1st plug sanded back to 3450' and dump 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 120 sx cement.

Maximum pressure 800 psi and shut in pressure 400 psi

Remarks: They recovered 2300' of 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
STATE CORPORATION COMMISSION

Signed Richard W. Lacey
(TECHNICIAN)

DATE 7-30-84

JUL 26 1984

INV. NO. 2756

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84