

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-109-27,038-0000

NW, Sec. 10, T 16 S, R 12 W10

2710 feet from N10 section line

1980 feet from W10 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6357

Lease Name Weber Well # 2.2

Operator: Weber Oil Co., Inc.  
Name & Address: Rt. 1, Box 72,  
Hoisington, Ks. 67544

County Barton

Well Total Depth 3336 feet 108.42

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" ~~3 1/2~~ feet 306'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Woodman-Dannitti Drilling Co. License Number 25

Address 1008 Douglas Bldg. Wichita, Ks. 67202

Company to plug at: Hour: 1:45 PM Day: 18 Month: 2 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Rich Wheeler

(company name) Woodman-Dannitti Drilling Co. (phone) 316-792-1922

were: Order 160 sh. 50% pozmix 4% Sol. - 3% Cal. Cl. & 8 5/8" plug. Spot w/dill stem w/ heavy mud between all plugs. 1st plug 3330' w/ 20 sh. 2nd plug C 790' w/ 80 sh. 3rd plug C 300' w/ 40 sh. 4th plug - solid bridge of hulls & plug C 40' w/ 10 sh.

Circulated 10 sh. in rat hole

Signed [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:45 PM Day: 18 Month: 2 Year: 19 83

ACTUAL PLUGGING REPORT 8 5/8" - 306' SP. case w/ 200 sh. cement - 2% Sol. - 3% Cal. Cl.

Ordered 160 sh. 50% pozmix - 4% Sol. - 3% Cal. Cl. & 8 5/8" plug. Spot w/dill stem w/ heavy mud between all plugs. 1st plug C 3330' w/ 20 sh. 2nd plug C 790' w/ 80 sh. 3rd plug C 300' w/ 40 sh. 4th plug - solid bridge of hulls & plug C 40' w/ 10 sh.

Circulated 10 sh. in rat hole.

Remarks: Drilled in to Arbuckle.

RECEIVED  
STATE CORPORATION COMMISSION  
3-14-83  
MAR 14 1983  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed [Signature]  
(TECHNICIAN)

INVOICED  
DATE MAR 28 1983  
INV. NO. 3792-4