

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20134-00-00  
Spot: W2E2NW Sec/Twnshp/Rge: 7-31S-16W  
4042 feet from S Section Line, 3646 feet from E Section Line  
Lease Name: TRUMMELL Well #: 1  
County: COMANCHE Total Vertical Depth: 5003 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	4996	0	WITH 150 SX CMT
SURF	8.625	344		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/06/2013 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: FIND BOTTOM & SAND OFF 50'. PLACE 5 SX CMT ON TOP OF SAND. PERFORATE 6" @ 1000' & CIRCULATE CMT UP 8 5/8" X 6" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/07/2013 11:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

2/6/13: BOTTOM PLUG: FOUND TD @ 4850'. SANDED BOTTOM TO 4800' & DUMPED 5 SX CMT ON TOP OF SAND WITH BAILER. TOP PLUG: PERFORATED 6" AT 1000'. RAN TBG TO 1024'. PUMPED 185 SX CMT CIRCULATING CMT TO SURFACE UP 6". NO RETURNS ON 10 3/4" X 6" ANNULUS. PULLED TBG OUT OF HOLE. TRIED TO TOP OFF 6" WITH 100 SX CMT. COULDN'T LOAD THE HOLE. WAITED 4 HOURS PUMPED 40 SX CMT DOWN 6". STILL COULDN'T LOAD IT. PUMPED 175 SX CMT DOWN 10 3/4" X 6" ANNULUS. MAXIMUM PUMP PRESSURE 400 PSIG. SHUT IN PRESSURE 200 PSIG. SDON. 2/7/13: TAGGED CMT INSIDE 6" @ 380'. PUMPED 85 SX CMT TOPPING OFF 8 5/8" X 6" CASINGS.

Perfs:

Remarks: CONTROL # 20130057-001 USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG  
*As well database indicates gas well.*

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED

FEB - 8 2013

KCC DODGE CITY

RECEIVED  
FEB 11 2013  
KCC WICHITA