

1030255

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 069-20,184 0000
SW SW, SEC. 17, T 26 S, R 29W/X
630 feet from NXX section line
4150 feet from W SE Corner of MXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151
Operator: Gear Petroleum, Inc.
Name & Address 300 Sutton Place
Wichita, KS 67202

Lease Name Unruh Well # 1-17
County Gray
Well Total Depth 5240 170.30 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A^X

Other well as hereinafter indicated _____

Plugging Contractor Cougar Drilling Co., Inc. License Number 5738

Address 555 North Woodlawn, Suite 114, Wichita, KS 67208

Company to plug at: Hour: 3:00 am Day: 23 Month: August Year: 19 84

Plugging proposal received from Gary Bagby
(company name) Cougar (phone) 316-685-7677

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1770' with 50 sx cement

2nd plug at 960' with 50 sx cement

3rd plug at 420' with 40 sx cement

solid bridge
4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Steve Dumont
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:00 am Day: 23 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1770' with 50 sx cement, 2nd plug at 960' with 50 sx cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form)
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 8-29-84

INV. NO. 3434
8-23

Signed Steve Dumont
(TECHNICIAN)