

1091042

TO: STATE CORPORATION COMMISSION

API NUMBER 15-069-20,184-~~000~~
C E/2 SW SW SEC. 17, T 26 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1130 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME UNRUH WELL # 1-17 OWWO

TECHNICIAN'S PLUGGING REPORT

COUNTY GRAY 170.30

OPERATOR LICENSE # 4868

WELL TOTAL DEPTH 5240 FEET

OPERATOR: ASHER ASSOCIATES, INC. PRODUCTION CSG: SIZE 4 1/2" @ 5098' WITH 125 SX

NAME AND 2350 E WILLIAMETTE LANE SURFACE CASING: SIZE 8 5/8" @ 416' WITH SX

ADDRESS GREENWOOD VILLAGE, CO 80121

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED STATE CORP COMMISSION

PLUGGING CONTRACTOR SWIFT SERVICES INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 1:45 PM DAY: 11 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM BILL WELLING

(COMPANY NAME) SWIFT SERVICES INC (PHONE) 785-798-2300

WERE: PERFS AT 4976-4995

ON 4/3/00 RAN WIRELINE TO 3683' BY ALLIED. COULD NOT GO ANY DEEPER WELL SANDED IN. ON 4/11

PERF TECH SET CIBP @ 995' FROM SURFACE. LOADED CASING PRESSURED TO 500#. PERFORATED AT

950'. SWIFT PUMPED 200 SX CEMENT. MAXIMUM PRESSURE AT 1200#. SHUT IN WITH 775#. CHECKED

BACKSIDE 1000# INSTANT PRESSURE. FOUND CEMENT IN BULL PLUG FROM PREVIOUS CEMENT JOB ON

BACKSIDE. PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 11 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT ON 4/3/00 RAN WIRE LINE TO 3683' BY ALLIED. COULD NOT GO ANY DEEPER

WELL SANDED IN. ON 4/11/00 PERF TECH SET CIBP @ 995' FROM SURFACE. LOADED CASING PRESSURED

TO 500#. PERFORATE CASING AT 950'. SWIFT PUMPED IN 200 SX CEMENT. MAXIMUM PRESSURE AT 1200#

SHUT IN WITH 775#. CHECKED BACKSIDE 1000# INSTANT PRESSURE. FOUND CEMENT IN BULL PLUG FROM

PREVIOUS CEMENT JOB ON BACKSIDE.

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 4/20/00

SIGNED

(TECHNICIAN)

FORM CP-2/3

INV. NO. 061611