

12-1-87

15-101-20308-0000

To: 1 070480
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion date 3/27/78
E/2 E/2 SE, SEC. 28, T 17 S, R 28 W/R
1320 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5258
Operator: Dane G. Hansen, Trust
Name & Address: Box 187
Logan, KS 67646

Lease Name Bryant Well # 1
County Lane Lane 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 1 Month: 12 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4300' Perfs at 4042-46' Elevation 2732' GL

1st plug sand back to 4000' with 4 sx cement,

2nd plug pump 200 sx Econolite.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3:15 p.m. Day: 1 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' with 4 sx cement on top of sand through bailer, shot pipe at 1420'

2nd plug pumped 100 sx ATL with 500 lbs. hulls down 4 1/2", Maximum pressure 800 psi and shut in 800 psi.

3rd plug pumped 100 sx ATL down 8 5/8", Maximum pressure 250 psi and shut in 100 psi

Remarks: Used ATL cement by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form)

do not observe this plugging.

DATE 12-8-87

INV. NO. 19203

Signed Dan Hoover (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas

DEC 7 1987
12-7-87
CONSERVATION DIVISION
Wichita, Kansas