

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21892-00-02
Spot: W2SESENE Sec/Twnshp/Rge: 31-9S-17W
2970 feet from S Section Line, 400 feet from E Section Line
Lease Name: SCHRANDT Well #: 3
County: ROOKS Total Vertical Depth: 3595 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3594		130 SX
SURF	8.625	166		120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/16/2013 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL Phone: (785) 259-1928

Proposed Plugging Method: Perforations at 905' cemented with 355 sx cwc base Dakota.
Production perforations: 3373' - 3576'.
Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2013 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated base of salt section at 2200' and Anhydrite at 1400'.
Ran tubing to 3260'. Swift services pumped 150 sx cement w/200 # hulls.
Pulled tubing to 2194' and pumped 100 sx cement w/100 # hulls.
Pulled tubing to 1009' and pumped 100 sx cement w/200 # hulls. Circulated cement.
PTOH and squeezed 30 sx cement. Maximum pressure 700 psi. Shut in pressure 400 psi.
Checked backside and there was instant pressure at 400 psi.

Perfs:

Top	Bot	Thru	Comments
3284	3515		

RECEIVED
JAN 22 2013
KCC WICHITA

Remarks: SWIFT SERVICES

Plugged through: TBG

District: 04

Signed Richard Williams
1/16/13 (TECHNICIAN)

CM

JAN 17 2013