

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20924-00-00
Spot: NENWSWNE Sec/Twnshp/Rge: 16-16S-33W
1556 feet from N Section Line, 2119 feet from E Section Line
Lease Name: DBY Well #: 5-16
County: SCOTT Total Vertical Depth: 4740 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 222 | | WITH 175 SX CMT |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/22/2013 5:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: TONY MARTIN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2350' WITH 50 SX CMT. 2ND PLUG AT 1600' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 01/22/2013 7:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 2350' WITH 50 SX CMT. 2ND PLUG AT 1600' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED

JAN 24 2013

KCC DODGE CITY

RECEIVED
JAN 31 2013
KCC WICHITA

RMW