

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20722-00-01
Spot: SENENWNW Sec/Twnshp/Rge: 29-16S-29W
4934 feet from S Section Line, 4257 feet from E Section Line
Lease Name: JENNISON A Well #: 1
County: LANE Total Vertical Depth: 4498 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4553	0	WITH 200 SX CMT
SURF	8.625	342		WITH 265 SX CMT

Well Type: EOR UIC Docket No: E27084.1 Date/Time to Plug: 01/25/2013 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: RICHARD L WALLGREN Company: DANE G HANSEN TRUST Phone: (785) 689-8111

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 65 SX CMT & 150# HULLS. PULL TBG TO ANHYDRITE & CIRCULATE CMT TO SURFACE. TRY TO PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/25/2013 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

****WELL HAD BEEN SQUEEZED WITH 350 SX CMT AT 1425', 250 SX CMT AT 1100', 625 SX CMT AT 990'.**** RUN TBG TO 3810' & SPOT 65 SX CMT & 150# HULLS. PULL TBG TO 2210' & PUMP 215 SX CMT. CMT CIRCULATED. PULL TBG & TOP OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 65 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
3872	4494		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES

Plugged through: TBG

District: 01

RECEIVED
JAN 31 2013

KCC DODGE CITY

Signed

Michael Maier
(TECHNICIAN)

RECEIVED
FEB 04 2013

KCC WICHITA

BDWY