

Operator Name Samuel Gary Jr. & Associates, Inc. Lease Name DUNN Well # 35-9

Sec. 35 Twp. 33S Rge. 19 East West County Comanche

Instructions: Show important tops and base of formation penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

<p>Drill Stem Tests Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (Attach Additional Sheets.)</p> <p>Sample Sent to Geological Survey <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No</p> <p>Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No</p> <p>Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (Submit Copy.)</p> <p>List all E. Logs Run: <input type="checkbox"/> dual induction <input type="checkbox"/> comp neutron-density <input type="checkbox"/> micro log <input type="checkbox"/> sonic log</p>	<p><input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Datum</p> <table style="width:100%; border-collapse: collapse;"> <tr> <th style="width:60%;">Name</th> <th style="width:20%;">Top</th> <th style="width:20%;">Datum</th> </tr> <tr> <td>STONE CORRAL</td> <td>981</td> <td>(960)</td> </tr> <tr> <td>WABAUNSEE</td> <td>3433</td> <td>(-1492)</td> </tr> <tr> <td>BASE HEEBNER SHALE</td> <td>4343</td> <td>(-2402)</td> </tr> <tr> <td>STARK SHALE</td> <td>4893</td> <td>(-2952)</td> </tr> <tr> <td>CHEROKEE SHALE</td> <td>5210</td> <td>(-3269)</td> </tr> <tr> <td>TOP MISS UNCONFORMITY</td> <td>5322</td> <td>(-3381)</td> </tr> </table> <p style="text-align: center; font-weight: bold; font-size: 2em;">ORIGINAL</p> <p style="text-align: center; font-weight: bold;">RECEIVED KANSAS CORPORATION COMMISSION</p> <p style="text-align: center; font-weight: bold;">SEP 14 2001</p> <p style="text-align: center; font-weight: bold;">CONFIDENTIAL KCC SEP 15 2001</p>	Name	Top	Datum	STONE CORRAL	981	(960)	WABAUNSEE	3433	(-1492)	BASE HEEBNER SHALE	4343	(-2402)	STARK SHALE	4893	(-2952)	CHEROKEE SHALE	5210	(-3269)	TOP MISS UNCONFORMITY	5322	(-3381)
Name	Top	Datum																				
STONE CORRAL	981	(960)																				
WABAUNSEE	3433	(-1492)																				
BASE HEEBNER SHALE	4343	(-2402)																				
STARK SHALE	4893	(-2952)																				
CHEROKEE SHALE	5210	(-3269)																				
TOP MISS UNCONFORMITY	5322	(-3381)																				

CASING RECORD New Used CONSERVATION DIVISION
WICHITA, KS

Report all strings set – conductor, surface, intermediate, production, etc.

Purpose of string	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
conductor	30"	20"		60'	10 sk grout	6 yds	
surface	12-1/4"	8-5/8"	24#	668'	65-35 poz Class A	225 100	6% gel, 3% CC & 1/4#/sk flocele 2% gel, 3% CC

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose:	Depth		Type of Cement	# Sacks Used	Type and Percent Additives
	Top	Bottom			
<input type="checkbox"/> Perforate					
<input type="checkbox"/> Protect Casing					
<input type="checkbox"/> Plug Back TD					
<input type="checkbox"/> Plug Off Zone					

Shots per Foot	PERFORATION RECORD – Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement, Squeeze Record (Amount and Kind of Material Used)	Depth

TUBING RECORD

Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No
------	--------	-----------	--

Date of First, Resumed Production, SWD or Inj. _____ Producing Method Flowing Pumping Gas Lift Other (Explain) _____

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
-----------------------------------	-----------	---------	-------------	---------------	---------

Disposition of Gas Vented Sold Used on Lease (If vented, submit ACO-18).

METHOD OF COMPLETION

Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____

ALLIED CEMENTING CO., INC.

8055

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

Federal Tax I.D.#
CONFIDENTIAL

SEP 13 2001 SERVICE POINT:

CONFIDENTIAL

Medicine Lodge

DATE <i>5-29-01</i>	SEC. <i>35</i>	TWP. <i>33s</i>	RANGE <i>19w</i>	CALLED OUT <i>3:00 pm</i>	ON LOCATION <i>5:00 pm</i>	JOB START <i>8:00 pm</i>	JOB FINISH <i>9:00 PM</i>
LEASE <i>Dunn</i>	WELL.# <i>33-9</i>	LOCATION <i>Coldwater, 5s, to</i>			COUNTY <i>Comanche</i>	STATE <i>Ks.</i>	
OLD OR NEW (Circle one)			<i>Jet, 4 more South 1w 2s</i>				

CONTRACTOR *Duke #1*
 TYPE OF JOB *Rotary Plug*
 HOLE SIZE *7 7/8* T.D.
 CASING SIZE _____ DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE *4 1/2 x 16.60* DEPTH *950'*
 TOOL _____ DEPTH _____
 PRES. MAX *100'* MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT *Fresh + Mud*

OWNER *SAM Gary Jr. + Assoc.*

CEMENT **ORIGINAL**

AMOUNT ORDERED *125 sx 60:40:6*

EQUIPMENT

PUMP TRUCK CEMENTER *Carl Balding*
 # *359-265* HELPER *Mike Rucker*
 BULK TRUCK
 # *242* DRIVER *Jason Tritt*
 BULK TRUCK
 # _____ DRIVER _____

RECEIVED <i>75</i>	@ <i>6.65</i>	<i>498.75</i>
POZ MIX <i>50</i>	@ <i>3.55</i>	<i>177.50</i>
GEL <i>6</i>	@ <i>10.00</i>	<i>60.00</i>
SEP 13 2001	@	
CONSERVATION DIVISION WICHITA, KS	@	
HANDLING <i>131</i>	@ <i>1.10</i>	<i>144.10</i>
MILEAGE <i>131 x 50</i>	@ <i>.04</i>	<i>262.00</i>
TOTAL		<i>1142.35</i>

REMARKS:

Release
 NOV 04 2003
 From
Confidential

SERVICE

Pump 40 sx - 950'
50 sx - 700'
10 sx - 40'
10 sx - Mouse Hole
15 sx - Rat Hole

DEPTH OF JOB <i>950'</i>		
PUMP TRUCK CHARGE		<i>520.00</i>
EXTRA FOOTAGE	@	
MILEAGE <i>50</i>	@ <i>3.00</i>	<i>150.00</i>
PLUG <i>Wooden</i>	@ <i>23.00</i>	<i>23.00</i>
TOTAL		<i>693.00</i>

CHARGE TO *SAM Gary Jr + Assoc % Larson Eng*
 STREET *562 W. Hwy 4*
 CITY *OLMITZ* STATE *KANSAS* ZIP *67564*

FLOAT EQUIPMENT

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE *1143.35*
 DISCOUNT *1143.35* IF PAID IN 30 DAYS

SIGNATURE *Mike Godfrey*

Mike Godfrey
 PRINTED NAME