


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Gray County. Sec. 22 Twp. 26 Rge. 29 E/W  
Location as "NE/CNW/SW" or footage from lines

SW SW NW  
Lease Owner Gear Petroleum Company  
Lease Name Hamlin Well No. 1  
Office Address 1325 Vickers KSB&T Bldg., Wichita 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plot

Date Well completed 4/24/78 19  
Application for plugging filed 4/24/78 19  
Application for plugging approved 4/24/78 19  
Plugging commenced 4/24/78 19  
Plugging completed 4/24/78 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas Jr.  
Producing formation Depth to top Bottom Total Depth of Well 5120

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	415	8 5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug at 400' with 50 sx 50/50 Poz, 6% gel  
Solid bridge at 40' with 10 sack 50/50 Poz, 6% gel  
5 sacks in rathole  
Job complete at 8 p.m. 4/24/78

RECEIVED  
STATE CORPORATION COMMISSION

MAY 02 1978

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.  
James C. Remsberg (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg  
James C. Remsberg  
200 Douglas Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 1 day of May, 1978

Mary Lou Taylor  
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



## DRILLERS LOG

OPERATOR: Gear Petroleum Company  
1325 Vickers KSB&T Building  
Wichita, Kansas 67202

LEASE: Hamlin No. 1  
SW SW NW 22-26S-29W  
Gray County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
200 Douglas Building  
Wichita, Kansas 67202

COMMENCED: 4/15/78

COMPLETED: 4/24/78

RTD: 5120'

CASING: 8-5/8" set at 415' with 300 sx cement

0' to 420' 12½ Surface Hole  
405' to 420' Cement  
420' to 1205' Sand & Shells  
1205' to 1305' Shale  
1305' to 1475' Sand  
1475' to 1860' Shale  
1860' to 2270' Shale & Shells  
2270' to 2575' Shale  
2575' to 2780' Shale & Lime  
2780' to 3590' Shale & Lime  
3590' to 3995' Lime & Shale  
3995' to 4210' Shale & Lime  
4210' to 4815' Lime & Shale  
4815' to 4920' Shale & Lime  
4920' to 4963' Lime  
4963' to 5000' Shale & Lime  
5000' to 5004' Lime  
5004' to 5100' Lime & Shale  
5100' to 5120' Shale & Lime  
RTD: 5120'

RECEIVED  
STATE COOPERATION COMMISSION  
MAY 02 1978  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state that the above and foregoing is a true and accurate copy of the log of the Hamlin No. 1 well for Gear Petroleum Company.

*James C. Remsberg*  
James C. Remsberg

Subscribed and sworn to me this  
1st day of May, 1978

*Mary Lou Taylor*  
Mary Lou Taylor, Notary

