

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-101-20845-0000

Give All Information Completely
 Make Required Affidavit

COUNTY Lane SEC. 28 TWP. 17S RGE. 28W E/W
 Location as in quarters or footage from lines:
NW NE NE 28-17S-28W

			+
	28		

Locate Well
 correctly on above
 Section Platt.

Lease Owner Mid Continent Energy Corp.
 Lease Name Bryant Well No. #1
 Office Address #712-120 S. Market
 Character of Well (Completed as Oil, Gas or Dry Hole): D.H.
 Date Well Completed 10-29-83
 Application for plugging filed 10-29-83
 Plugging commenced 10-29-83
 Plugging completed 10-29-83
 Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom _____ T.D. 4600 RTD

Show depth and thickness of all water, oil and gas formations. 4603 LTD

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put In	Pulled Out
surface	8 jts. new	20 #	17' 8"	5/8" set	@ 326'	

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged w/50 sx., @ 2130', 50 sx. @ 1620'
 40 sx. @ 360', 10 sx. @ 40', 15 sx. in rat hole
 10 sx. in mouse hole, 175 sx. total, 60-40 pos mix
 3% c.c., 2% gel, started @ 9:00 a.m. completed
 @ 1:00 p.m. Steve Durrant state plugger

RECEIVED
 STATE CORPORATION COMMISSION
 DEC - 1 1983
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Warrior Drilling Co. Rig #2

STATE OF Kansas COUNTY OF Sedgwick, ss.
F.W. Shelton, Jr., (employee of owner) ~~or (owner or operator)~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) F.W. Shelton, Jr.
 F.W. Shelton, Jr., Vice Pres.
 (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of October, 19 83

MARTHA E. GUSTIN
 NOTARY PUBLIC
 STATE OF KANSAS

Martha E. Gustin
 Martha E. Gustin Notary Public.

My Commission expires: 4-15-85

WELL LOG

15-101-20845-0000

October 29, 1983

Bryant #1
NW NE NE Sec. 28-17S-28W
Lane County, Kansas

OPERATOR: Mid-Continent Energy Corporation
CONTRACTOR: Warrior Drilling Co., Rig #2
COMMENCED: October 20, 1983
COMPLETED: October 29, 1983

8 5/8" @ 326' w/200 sx. 60-40

0	45	Surface Clay
45	165	Sand & Clay
165	328	Clay & Sand
328	2128	Clay & Shale
2128	2165	Anhydrite
2165	2747	Shale & Clay
2747	3790	Shale
3790	4135	Shale & Lime
4135	4220	Lime & Shale
4220	4383	Shale & Lime
4383	4600	Lime
4600		RTD
4603		LTD

D & A Plugged w/175 sx. 60-40

We certify that the above and foregoing is a true and correct copy of the log on the #1 Bryant located in Lane County, Kansas.

WARRIOR DRILLING CO.,

F.W. Shelton, Jr.
F.W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 29th day of October, 1983.

MARTHA E. GUSTIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPL. EXPIRES 4-15-85

RECEIVED
STATE CORPORATION COMMISSION
DEC - 1 1983
CONSERVATION DIVISION
Wichita, Kansas

Martha E. Gustin
Martha E. Gustin Notary Public