

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21035-0000

LEASE NAME Pelton #1-29

WELL NUMBER _____

SPOT LOCATION C E/2 SE/4

SEC. 29 TWP. 17S RGE. 28W (E) or (W)

COUNTY Lane

Date Well Completed _____

Plugging Commenced 11/13/85

Plugging Completed 1/3/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KRM Petroleum Corp.

ADDRESS 1900 Grant St. #300, Denver, Co. 80203

PHONE # (303) 830-6601 OPERATORS LICENSE NO. 6420

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	307'	none
				5 1/2"	4648'	2503'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4450' & 5 sacks cement. Shot pipe at 3021', & 2503'

Pulled 60 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 15 gel, 1 hull, plug, & 175 sacks cement.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss. STATE COMMISSIONER

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso


(Address) Box 347, Chase, Ks. 67524

JAN 9 1986
1-9-86
CONSERVATION DIVISION
Wichita, Kansas


SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 86

James Turner
Notary Public

My Commission expires:



ALDEBARAN



DRILLING CO. INC.

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

WELL LOG

WELL NAME: PELTON #1-29

WELL LOCATION: C E/2 SE/4

SEC. 29-17S-28W LANE COUNTY, KS.

OPERATOR: KRM PETROLEUM CORPORATION

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMMENCED: 9-10-84

COMPLETED: 9-19-84

190 sks set at 307'

CASING RECORD: 60-40 poz 2% gel
3% cc. 8 5/8" 24 wt. new
75 sks. set at 4648'
5 1/2" 17 wt. used
50-50 poz 2% gel 18% salt
3/4 of 1 1/2 CBZ

<u>FORMATION:</u>	<u>FROM:</u>	<u>TO:</u>
Sand-Clay	0	987'
Sand-Shale	987'	1606'
Shale	1606'	1699'
Shale-Sand	1699'	2028'
Shale-Anhydrite	2028'	2287'
Shale-Lime	2287'	4650'

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
C E/2 SE/4, SEC. 29-17S-28W LANE COUNTY, KANSAS TO THE BEST OF MY
KNOWLEDGE AND BELIEF.

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1985

CONSERVATION DIVISION
Wichita, Kansas

ALDEBARAN DRILLING CO., INC.
WAYNE L. KIRKMAN
PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 24th DAY OF SEPTEMBER, 1984

KATHLEEN G. QUINN
STATE NOTARY PUBLIC
MY APPOINTMENT EXPIRES MARCH 20, 1987
My Appt. Exp.

Kathleen G. Quinn
KATHLEEN G. QUINN