

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,561-0000

LEASE NAME Bryant 'B'

WELL NUMBER 1

2310 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 30 TWP. 17 RGE. 28 (X) or (W)

COUNTY Lane

Date Well Completed 11/22/90

Plugging Commenced 7:15 P.M. 11/22/90

Plugging Completed 9:00 P.M. 11/22/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 22, 1990 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4592

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

1st Plug @ 2190' w/50 sx

5th Plug @ 40' w/10 sx

2nd Plug @ 1350' w/50 sx

Rat Hole w/15 sx

3rd Plug @ 675' w/50 sx

Total 225 sx 60/40 Poz, 6% Gel,

4th Plug @ 245' w/50 sx

1/4# floseal per sk.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, Kansas 67665

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales, Manager

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dane G. Bales

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN to before me this 5th day of December, 19 90

STATE CORPORATION COMMISSION
12-18-90
DEC 18 1990
CONSERVATION DIVISION
Wichita, Kansas

Betty Jane Bittel
Notary Public

My Commission Expires: July 17, 1992



EFFECTIVE DATE: 11-5

State of Kansas 101-21,561-0000
NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 13, 1990
month day year

N/2 NW SE Sec 30 Twp 17s S, Rg 28 East
West

OPERATOR: License # 5285
Name: The Dane G. Hansen Trust
Address: P. O. Box 187
City/State/Zip: Logan, Kansas 67646
Contact Person: Dane G. Bales
Phone: 913-689-4816

2310 feet from South line of Section
1980 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5783
Name: Galloway Drilling Co., Inc.

County: Lane
Lease Name: Bryant 'B' Well #: 1
Field Name: WC

Well Drilled For: Well Class: Type Equipment:
X. Oil ... Inj ... Infield ..X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... O/WO ... Disposal ..X Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes X.. no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 330'
Ground Surface Elevation: N.A. feet MSL

If O/WO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Domestic well within 330 feet: ... yes X.. no
Municipal well within one mile: ... yes X.. no
Depth to bottom of fresh water: 150'
Depth to bottom of usable water: 1350'

Directional, Deviated or Horizontal wellbore? ... yes X.. no
If yes, total depth location: _____

Surface Pipe by Alternate: ... 1 ..X 2
Length of Surface Pipe Planned to be set: 200
Length of Conductor pipe required: None
Projected Total Depth: 4500'

Formation at Total Depth: Mississippian
Water Source for Drilling Operations: Contractors decision
... well ... farm pond ... other

DWR Permit #: _____
Will Cores Be Taken?: ... yes X.. no
If yes, proposed zone: _____

200' Alt. II Req.

Exp. 4/30/91

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
I do so certify that the following minimum requirements will be met:

Pusher: Carl McQuire

SPUD DATE 11-14-90 INIT. SP

LENGTH SURFACE PLANNED 215 of 8 1/2

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2 @ 215 CONDUCTOR
ANHYDRITE T- 2148 B- 2178 ELEVATION

TD 4592 FORMATION _____

RAN PIPE @	DV TOOL	ALT II DONE
SX	SX	Y N
Arbuckle Plug @	Ft. W/	SX
Hug./Council @	Ft. W/	SX
Anhydrite Base @	Ft. W/	<u>50</u> SX
1/2 Base Anhyd. @	<u>1350</u> Ft. W/	<u>50</u> SX
1/2 Plug @	<u>675</u> Ft. W/	<u>50</u> SX
Bottom Surface @	<u>245</u> Ft. W/	<u>50</u> SX
40' Plug @	<u>40</u> Ft. W/	<u>10</u> SX

RAT HOLE CIRC/W/ 15 SX MOUSE HOLE W/ --- SX

WATER WELL --- SX (Irr. Well) Pond ---
Hauling ---

TECHNICIAN CA DATE 11-18-90

TYPE OF CEMENT 60/40 Poz 670 1/15 F.S.P. - Set

STARTING TIME 6:00 (AM/PM) DATE 11-22-90

COMPLETION TIME 9:00 (AM/PM) DATE 11-22-90

CEMENT COMPANY Allied