

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Comanche County, Sec. 20 Twp. 34 Rge. 17 E/W
Location as "NE/CNW/SW" or footage from lines
NE SW NW

Lease Owner Mid-Continent Energy Corporation
Lease Name Ehrlich Well No. 1

Office Address 712 One Twenty Building, Wichita 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed 5/9/79 19
Application for plugging filed 5/9/79 19
Application for plugging approved 5/9/79 19
Plugging commenced 5/9/79 19
Plugging completed 5/9/79 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations. 6232 T.D.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-----|--------|--------|------------|
| | Surface | 0 | 427 | 8-5/8" | yes | no |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Bottom plug @ 700' with 50 sacks 50/50 Poz, 6% gel
Middle plug @ 400' with 40 sacks 50/50 Poz 6% gel
Top & bridge @ 40' with 12 sacks 50/50 Poz, 6% gel
3 sacks in rathole
Job complete @ 4:30 p.m. 5/9/79

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1979

(If additional description is necessary, use BACK of this sheet) DIVISION
Wichita, Kansas

Name of Plugging Contractor Slawson Drilling Company, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
James C. Remsberg of Slawson Drilling Co., Inc. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
James C. Remsberg
200 Douglas Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of May, 1979

Mary Lou Zaylor
Mary Lou Zaylor Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

OPERATOR: Mid-Continent Energy Corporation
 712 One Twenty Building
 Wichita, Kansas 67202

LEASE: Ehrlich No. 1
 NE SW NW Sec. 20-34S-17W
 Comanche County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 4/20/79

COMPLETED: 5/9/79

RTD: 6232'

SURFACE CASING: 8-5/8" set at 427' with 450 sx cement
 CONDUCTOR PIPE: 76' of Conductor pipe set

0' to 76' Conductor pipe
 76' to 110' Shale
 110' to 430' Sand & Shale (12 1/2" Surface Hole)
 430' to 720' Sand & Shale
 720' to 1000' Shale
 1000' to 1660' Shale & Shells
 1660' to 2210' Shale
 2210' to 4465' Lime & Shale
 4465' to 4595' Lime
 4595' to 4900' Lime & Shale
 4900' to 4985' Lime & Shale (LKC)
 4985' to 5194' Lime
 5194' Cherokee
 5194' to 5267' Lime
 5267' Mississippian
 5267' to 5315' Mississippian
 5315' to 5325' Lime (Miss)
 5325' to 5470' Miss
 5470' to 5550' Lime & Shale
 5550' to 5685' Lime
 5685' to 5760' Lime & Shale
 5760' to 5905' Lime
 5905' to 5985' Viola Lime
 5985' to 6130' Lime
 6130' to 6140' Shale & Sand (Simpson)
 6140' to 6175' Shale
 6175' to 6232' Lime & Shale
 6232' RTD (Arbuckle)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 18 1979
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS
 COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the Ehrlich No. 1 log for Mid-Continent Energy Corp.

James C. Remsberg
 James C. Remsberg

Subscribed & sworn to me this 15th day of May, 1979

Mary Lou Taylor
 Mary Lou Taylor, Notary

My Commission expires January 17, 1981

