

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23294-00-00
Spot: NESWNENW Sec/Twnshp/Rge: 8-10S-21W
900 feet from N Section Line, 1800 feet from W Section Line
Lease Name: GRECIAN A Well #: 1
County: GRAHAM Total Vertical Depth: 3893 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3892		470 SX
SURF	8.625	223		150 SX
TI	2.375	3850		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2012 11:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement, 11 sx gel spacer and 400 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2012 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 50 sx cement w/200 # hulls followed by 11 sx gel spacer.
Pumped 225 sx cement w/200 # hulls. Shut in pressure 250 psi.
Visually checked backside. Cement to surface.

GPS: 39.20279 -099.69203

Perfs:

Top	Bot	Thru	Comments
3839	3844		
3713	3716		
3626	3640		
3597	3640		
3553	3556		

RECEIVED
DEC 31 2012
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING TICKET # 6329

Plugged through: CSG

District: 04

Signed Pat Bedore
01/09/13 (TECHNICIAN)

CM

DEC 26 2012