

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-08282-00-00  
Spot: SESWSWNW Sec/Twnshp/Rge: 25-14S-15W  
2833 feet from S Section Line, 4937 feet from E Section Line  
Lease Name: HARBAUGH J I A Well #: 6  
County: RUSSELL Total Vertical Depth: 3174 feet

Operator License No.: 31250  
Op Name: HUXMAN, RICHARD LEON DBA KSC O  
Address: PO BOX 567  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3167		10 SX
SURF	12.5	781		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/18/2013 9:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Revd. from: LEON HUXMAN Company: KSC OIL Phone: (785) 483-0567

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls and 20 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/18/2013 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 780' and 300'.  
Ran tubing to 3000' and pumped 20 sx gel followed by 75 sx cement w/200 # hulls.  
Pulled tubing to 1450' and pumped 130 sx cement w/200 # hulls.  
Pulled tubing to 800' and pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 300'. Circulated cement to surface with 60 sx cement.  
Pulled tubing. Topped off with 15 sx cement.  
Tied to surface casing and pressured to 300 psi. Would not take any cement.

GPS: 38.80609 -098.94631

Perfs:

Top	Bot	Thru	Comments
3167	3174		
2957	2960		
2943	2947		
2884	2888		

RECEIVED  
JAN 24 2013  
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING TICKET # 6366

Plugged through: ESG TB<sup>6</sup>

District: 04

Signed Bruce Rodie  
2/02/13 (TECHNICIAN)

CM

JAN 22 2013