

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20914-00-00  
Spot: NENENW Sec/Twnshp/Rge: 29-1S-26W  
330 feet from N Section Line, 2310 feet from W Section Line  
Lease Name: CHAMBERS Well #: 10  
County: DECATUR Total Vertical Depth: 3675 feet

Operator License No.: 8981  
Op Name: ADECO, INC.  
Address: BOX 873  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3666		435sx
SURF	8.625	229		175sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/27/2012 10:30 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Revd. from: HAROLD BELLERIVE Company: ADECO INC. Phone: (785) 635-4531

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
8 5/8" surface casing set at 229' w/175 sx cement. 4 1/2" production casing set at 3666' w/435 sx cement.  
TD 3675'. PBSD at 3396'. Perforations unknown.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/27/2012 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 1362' and 1980'  
Ran tubing to 3315' and pumped 80 sx cement w/200 # hulls.  
Pulled tubing to 2158' and pumped 70 sx cement w/150 # hulls.  
Pulled tubing to 1064' and pumped 80 sx cement w/150 # hulls. Circulated cement to surface.  
Pulled tubing to surface and topped off with 20 sx cement.  
Connected to 8 5/8" surface casing and pumped 20 sx cement. Maximum pressure 600 psi.

GPS: 39.94278 -100.26469

Perfs:

Top	Bot	Thru	Comments
3261	3266		

RECEIVED  
JAN 16 2013

KCC WICHITA

Remarks: SOS TICKET # 660

Plugged through: TBG

District: 04

Signed Darrel Dipman  
4/30/13 (TECHNICIAN) CM

DEC 27 2012