

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-01069-00-00  
Spot: N2SWSE Sec/Twnshp/Rge: 31-17S-10W  
986 feet from S Section Line, 1976 feet from E Section Line  
Lease Name: MORAN A Well #: 9  
County: ELLSWORTH Total Vertical Depth: 3266 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2775		
PROD	4.5	3231		135 SX
SURF	8.625	213		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/02/2013 9:30 AM  
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELLL SERVICE, INC.  
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 272-4996

Proposed  
Plugging  
Method:

SEE BELOW. THIS WELL HAD FAILED MIT FOR TA STATUS ON 12-6-2012--CASING LEAK.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/02/2013 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU--SET CIBP AT 2775' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1250', 950', AND 263'. RUN TUBING TO 1250' AND PUMP 35 SX'S CEMENT. PULL TUBING PARTIALLY UP -- LET SET FOR AWHILE -- LOWER TUBING BACK -- TAGGED AT 1245'. PULL TUBING TO 950' AND PUMP 3 SX'S GEL FOLLOWED BY 35 SX'S CEMENT. PULL TUBING TO 263' AND PUMP 3 SX'S GEL FOLLOWED BY CEMENT -- CIRCULATED TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3231	3266	OH	

RECEIVED  
JAN 17 2013

Remarks: 60-40 POZ, 4% GEL. ALLIED TICKET #59215. FAILED MIT FOR TA STATUS.

Plugged through: TBG

KCC WICHITA

District: 02

Signed

*Virgil Clothier*  
1/20/13

(TECHNICIAN)

JK