

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22685-00-00
Spot: SWSNW Sec/Twnshp/Rge: 32-15S-11W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BORELL - C Well #: 1
County: RUSSELL Total Vertical Depth: 3400 feet

Operator License No.: 31086
Op Name: RICHLAN DRILLING, A GENERAL PAR
Address: 598 2ND AVE
BEAVER, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3395		100 SX
SURF	8.625	503		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2012 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICK SCHREIBER Company: RICHLAN DRILLING Phone: (620) 793-2032

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls and 8 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/10/2012 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 640' and 480'.
Ran tubing to 3217'. Tied to tubing and pumped 8 sx gel followed by 40 sx cement.
Pulled tubing to 1350' and pumped 50 sx cement.
Pulled tubing to 639' and pumped 45 sx cement w/100 # hulls. Circulated cement to surface on casing. Shut in casing.
Circulated cement out surface pipe with 90 sx cement.
Pulled tubing and topped off with 15 sx cement.

GPS: 38.70505 -098.57282

Perfs:

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie
6/10/13
(TECHNICIAN)

CM

RECEIVED
DEC 28 2012
KCC WICHITA

DEC 18 2012