

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20488-00-00  
Spot: NWSEW Sec/Twnshp/Rge: 22-10S-25W  
3630 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: BRUNGARDT B Well #: 3  
County: GRAHAM Total Vertical Depth: 4010 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4008		200 SX
SURF	8.625	225		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2012 10:30 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: MARK LEIKER Company: BEREN CORPORATION Phone: (316) 772-8649

Proposed Plugging Method: 8 5/8" surface casing set @ 225' w/225 sx cement. 5 1/2" production casing set at 4008' with 200 sx cement. TD 4010', PBTD 3943'. Perforations: 3870' - 3878'. 5 1/2" casing squeezes: 1415' - 1447 & 1898' - 1930'. Squeezed with 200 sx cement. (squeezed together) 1450' - 1600' squeezed with 200 sx cement and 2794' - 2827' squeezed with 250 sx cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/18/2012 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 3850' and pumped 150 sx cement w/250# hulls.  
Pulled tubing to 2300' and pumped 120 sx cement w/150 # hulls.  
Pulled tubing to 1200' and pumped 90 sx cement w/100 # hulls. Cement to surface.  
Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 10 sx cement.  
Connected to 8 5/8" surface casing and pumped 70 sx cement.

GPS: 39.17068 -100.10241

Perfs:

Remarks: QUALITY WELL SERVICE TICKET # 3767.

Plugged through: TBG

RECEIVED  
JAN 16 2013  
KCC WICHITA

District: 04

Signed Darrel Dipman (TECHNICIAN) CM  
1/30/13

DEC 20 2012