

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-10033-00-00  
Spot: NENENE Sec/Twnshp/Rge: 5-29S-38W  
5036 feet from S Section Line, 410 feet from E Section Line  
Lease Name: MCGANNON Well #: 1  
County: GRANT Total Vertical Depth: 4601 feet

Operator License No.: 5952  
Op Name: BP AMERICA PRODUCTION COMPANY  
Address: 2225 W OKLAHOMA AVE  
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	4596	0	WITH 1000 SX CMT
SURF	20	513		WITH 1000 SX CMT

Well Type: SWD UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/27/2012 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: JOEL FLORES Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: 50 SX CMT HOT PLUG @ 4000'. PUMP 20 SX CMT @ 1750'. PERFORATE @ 575'. SET CMT RETAINER @ 500'+/- SQUEEZE WITH 80 SX CMT OR CIRCULATE CMT TO SURFACE. FILL 5 1/2" WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/02/2013 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

12/27/12: PUMP 50 SX CLASS C CEMENT & 2% CC @ 4030'. LOAD CASING WITH WATER. STAYED FULL. 12/28/12: BOTTOM PLUG HOLDING. SPOT 40 SX CMT AT 1750'. FULL CIRCULATION. TOOH W/TBG. RAN 3.9" GAUGE RING IN 5 1/2" CASING TO 650'. NO PROBLEM. RAN 4.9" GAUGE RING IN 5 1/2" CASING. SET DOWN ON 5 1/2" CASING STUB @ 445'. TOP OF PARTED CASING AT 414'. PERFORATE @ 561' IN 5 1/2" LINER. TOOH W/414' OF PARTED 5 1/2" LINER. SET 7" CMT RETAINER AT 400'. RUN TBG & STING IN. INJECTION RATE 2 BPM @ 100 PSI. NO BLOW OR CIRCULATION UP 7" OR 20". PUMP 150 SX CLASS C CEMENT THROUGH RETAINER INTO PERFS @ 561' @ 300# INCREASING TO 800#. ISIP = 400#. STING OUT OF RETAINER & CIRCULATE 7" FULL OF CMT FROM 400' TO 0' & TOP OFF WITH TOTAL OF 90 SX CMT. CANNOT PUMP 7" X 20" ANNULUS DUE TO CEMENTED IN ON TOP.

Perfs:

Top	Bot	Thru	Comments
4150	4170		
4025	4333		

RECEIVED  
JAN 11 2013  
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: \_\_\_\_\_

Signed: \_\_\_\_\_

(TECHNICIAN)

cc to UIC 1/10/13

AMDP