

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23391-00-00  
Spot: NWNWNWNW Sec/Twnshp/Rge: 21-9S-22W  
120 feet from N Section Line, 240 feet from W Section Line  
Lease Name: BRASSFIELD UNIT Well #: 1  
County: GRAHAM Total Vertical Depth: 4041 feet

Operator License No.: 5135  
Op Name: FARMER, JOHN O., INC.  
Address: 370 W WICHITA AVE PO BOX 352  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1910		110 SX
PROD	5.5	4067		125 SX
SURF	8.625	219		160 SX
T1	2.875	4035		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/12/2012 9:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Revd. from: DUANE EICHMAN Company: JOHN O FARMER INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement , 11 sx gel spacer and 500 # hulls.  
Port Collar at 1910' with 110 sx cement.  
Production perforations at 3690' - 4024'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/12/2012 11:00 AM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

Hooked to 8 5/8" x 5 1/2" annulus and pressured up immediately.  
Hooked to 5 1/2" casing and pumped 50 sx cement w/100 # hulls followed by 11 sx gel spacer.  
Pumped 350 sx cement w/400 # hulls.

GPS: 39.26279 -099.79062

**Perfs:**

Top	Bot	Thru	Comments
4020	4024		
4011	4016		
4004	4008		
3780	3784		
3690	3694		

RECEIVED  
DEC 31 2012  
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING TICKET # 6246

Plugged through: CSG

District: 04

Signed

Pat Bedore  
(TECHNICIAN)

CM

DEC 26 2012