

15-101-21035-0000

1 070118
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Comp. 9-14-84

C E/2 SE, SEC. 29, T 17 S, R 28 W/EA

1320 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6420

Lease Name Pelton Well # 1-29

Operator: KRM Petroleum Corp.
Name & Address 1900 Grant Street, Suite 300
Denver, CO 80203

County Lane 151.13

Well Total Depth 4650 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 3 Month: January Year: 19 86

Plugging proposal received from Ron Hoover (not on location)

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4648' Perfs at 4562'; 4659'; 4500-04'

1st plug sand back to 4450' and dump 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pump 175 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 pm Day: 3 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 175 sx cement.

Maximum pressure 500 psi and shut in 200 psi

Remarks: Recovered 2503' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed Dan Gooden
(TECHNICIAN)

DATE JAN 14 1986

INV. NO. 12058

JAN 13 1986
1-13-86
CONSERVATION DIVISION
Wichita, Kansas