

1 060046

11-22

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,561-0000

N/2 NW SE, SEC. 30, T 17 S, R 28 W/E

2310 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Bryant "B" Well # 1

Operator: The Dane G. Hansen Trust

County Lane 149.24

Name & Address P.O. Box 187

Well Total Depth 4592 feet

Logan, KS 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Galloway Drilling Company, Inc. License Number 5783

Address 105 S. Broadway, #340, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 22 Month: 11 Year: 19 90

Plugging proposal received from Carl McGuire

(company name) Galloway Drilling Company, Inc. (phone) 316-263-1793

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2148-78'

1st plug at 2190' with 50 sx cement, 2nd plug at 1350' with 50 sx cement,

3rd plug at 675' with 50 sx cement, 4th plug at 245' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9 a.m. Day: 22 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2190' with 50 sx cement,

2nd plug at 1350' with 50 sx cement,

3rd plug at 675' with 50 sx cement,

4th plug at 245' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

NOV 27 1990 11-27-90 CONSERVATION DIVISION Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel w/ floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(XXX) (do not) observe this plugging.

DATE 12-6-90

Signed Case Morris (TECHNICIAN)

INV. NO. 30157