

3-4

1 080052

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,542-0000  
70' N of  
SE NE SW, SEC. 30, T 17 S, R 28 W/E  
1720 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063  
Operator: Energy Exploration, Inc.  
Name & Address  
1002 South Broadway  
Wichita, KS 67211

Lease Name Bryant Well # 1A  
County Lane 150.67  
Well Total Depth 4636 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665

Company to plug at: Hour: 9 a.m. Day: 4 Month: 3 Year: 19 90

Plugging proposal received from Tom Alm

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2193'  
1st plug at 2200' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,  
3rd plug at 240' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Mike Spain  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:45 a.m. Day: 4 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement,  
2nd plug at 1400' with 80 sx cement,  
3rd plug at 240' with 40 sx cement,  
4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED (If you did not observe this plugging.)

DATE 3-14 MAR 19 1990 3-9-90

INV. NO. 27638  
CONSERVATION DIVISION  
Wichita, Kansas  
3-4

Signed Mike Spain  
(TECHNICIAN)