

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21470-00-01
Spot: SWNWSE Sec/Twnshp/Rge: 30-17S-28W
1680 feet from S Section Line, 2350 feet from E Section Line
Lease/Unit Name: BRYANT OWWO Well Number: 1
County: LANE Total Vertical Depth: 4670 feet

Operator License No.: 31251 Conductor Pipe: Size feet:
Operator Name: WABASH ENERGY CORPORATION Surface Casing: Size 8.625 feet: 374 WITH 190 SX CMT
Address: PO BOX 595 Production: Size 5.5 feet: 4653 WITH 150 SX CMT
LAWRENCEVILLE, IL 62439 11/30 Liner: Size feet: 151.78

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/29/2000 9:50 AM
Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC
Proposal Rcvd. from: JEFF Company: PLAINS INC Phone: (782) 798-3995

Proposed Plugging Method: 1ST PLUG AT 2190' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 40 SX CMT. 3RD PLUG AT 600' WITH 80 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/30/2000 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4551-44 & 4547-49'. PUMP 35 SX CMT AND 200# HULLS TO BOTTOM. PULLING UNIT BROKE CABLE WHILE PULLING STRETCH. ON 11/30/00 SHOT OFF AT 1200' AND COULDN'T PULL FREE PUMPED 80 SX CMT AND FLUID CIRCULATED. TRIED TO PULL CASING AGAIN AND WOULDN'T COME LOOSE. SHOT OFF AT 930' AND PULLED 85,000# OVER STRING WEIGHT AND STILL WOULDN'T COME LOOSE. SHOT AT 650' AND CAME LOOSE. PULLED 2 JOINTS AND PUMPED 80 SX CMT AT 470'. FLUID CIRCULATED. PULLED REST OF CASING AND TOPPED OFF WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 650' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Michael Maier (TECHNICIAN)
INVOICED RECEIVED
STATE CORPORATION COMMISSION
DATE 12/11/00 DEC 7 2000
INV. NO. 200106111312-7-00
CONSERVATION DIVISION
Wichita, Kansas
DEC 06 2000
Form CP-2/3