

1 110095

12-9-87

To:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING SECTION  
 200 COLORADO DERBY BUILDING  
 WICHITA, KANSAS 67202

API NUMBER 15- 101-21,428-~~000~~  
 SW NW SE, SEC. 31, T 17 S, R 28 ~~W~~<sup>XX</sup>  
 1650 feet from S section line  
 2310 feet from E section line  
 Lease Name Maser Estate Well # 1  
 County Lane 149.83  
 Well Total Depth 4610 feet  
 Conductor Pipe: Size feet  
 Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A X

Other well as hereinafter indicated       

Plugging Contractor Mallard JV, Inc. License Number 4958

Address Box 1009, McPherson, KS 67460

Company to plug at: Hour: 2:40 a.m. Day: 9 Month: 12 Year: 1987

Plugging proposal received from Arnie Hess

(company name) Mallard JV, Inc. (phone) 316-241-4640

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2777' KB  
Anhydrite 2159'

1st plug at base of Anhydrite with 50 sx cement,

2nd plug at 1350' with 80 sx cement,

3rd plug at 30' below base of surface pipe with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
 (TECHNICIAN)

Plugging Operations attended by Agent?: All        Part        None X

Operations Completed: Hour: 6:30 a.m. Day: 9 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2188' with 50 sx cement,

2nd plug at 1350' with 80 sx cement,

3rd plug at 240' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

**INVOICED** (If additional description is necessary, use BACK of this form.)  
 (I did not observe this plugging.)

DATE 12-14-87

INV. NO. 19259

Signed James R. Gray  
 TECHNICIAN