

To: 1 041286
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

2-19

API NUMBER 15- 033-20,331 ~~0000~~

C NE NE, SEC. 19, T 34 S, R 17 W/4

660 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 30313

Lease Name Hass Well # 1

Operator: JHL Energy, Inc.

County Comanche 190.13

Name & Address 1428 S. Leecrest

Well Total Depth 5850 feet

Wichita, KS 67209-1132

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 472

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 19 Month: 2 Year: 19 98

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5345' w/150 sx cement, PBTD 5276', Perfs at 5238-45, 5250-54'

1st plug sand back to 5175' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by W. Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 19 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug sanded back to 5140' and dumped 4 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3450' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE FEB 26 1998
INV. NO. 50159
Signed Stephen J. Pfeiffer (TECHNICIAN)

RECEIVED
02-25-98
CONSERVATION DIVISION
Wichita, Kansas