

1 080224

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,407 0000
SE/4, SEC. 18, T. 34 S, R 17 W/P

TECHNICIAN'S PLUGGING REPORT

640 feet from ~~W&X~~ section line
520 feet from ~~W&X~~ section line

Operator License # 5171

Lease Name Rafler Well # 1

Operator: TXO Production Corp.

County Comanche

Name & Address 200 West Douglas, Suite 300

Well Total Depth 5809 188.79 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 457

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 19 Month: September Year: 19 84

Plugging proposal received from Norman Voth

(company name) Kelso (phone) 316-938-2457

were: Cement retainer (1/2 sack hulls and 25 sx cement and a plug set at 5200' 3-1-84 -

has been drilled out) 4 1/2" set at 5495' PBTD 5275' Perfs 5280-88 & 5250-58'

1st plug pump 35 sx cement to bottom

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls release 8 5/8"
rubber plug and pump 150 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:25 am Day: 19 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 5495' PBTD 5275' Perfs 5280-88' & 5250-58'

1st plug pumped 35 sx cement to bottom, 2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx
cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in pressure 350 psi STATE CORPORATION COMMISSION

OCT 01 1984

CONSERVATION DIVISION

Remarks: They recovered 3200' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form.)

INVOICED
Do not destroy or lose this plugging.

DATE 10-8-84

Signed J. H. Metz 50
(TECHNICIAN)

INV. NO. 4080

9-19