

1 080225

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,424 0000  
SW/4, SEC. 17, T 34 S, R 17 W/E  
660 feet from ~~XXX~~ SE Corner of section line  
2970 feet from ~~XXX~~ W SE Corner of section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5171

Lease Name Ehrlich "B" Well # 1 SWD  
County Comanche

Operator: TXO Production Corporation  
Name & Address 200 West Douglas, Suite 300  
Wichita, KS 67202

Well Total Depth 5520 179.40 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 600

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 19 Month: September Year: 19 94

Plugging proposal received from Norman Voth

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 5523 PBD 5482' Perfs 5240-45' 5253-58' 5330' 5340' & 5350'

1st plug pump 35 sx cement to bottom

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release  
8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:00 am Day: 19 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 5523' PBD 5482' Perfs 5240-45' 5253-58' 5330' 5340'

and 5350'

1st plug pumped 35 sx cement to bottom, 2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement,  
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement

OCT 01 1984

Maximum pressure 600 psi and shut in pressure 300 psi

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: They recovered 3508' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun.  
(if additional description is necessary, use BACK of this form.)

**INVOICED** (if needed) observe this plugging.

DATE 10-8-84

Signed J. H. Metz SA  
(TECHNICIAN)

INV. NO. 4082

9-19