

1060151

TO: STATE CORPORATION COMMISSION 3-26

API NUMBER 15-083-20,180 0000
C SW SW SEC. 3, T 21 S, R 24 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE
WICHITA STATE OFFICE BLDG., 130 S. MARKET 4620 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME VAN VLEET WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY HODGEMAN

OPERATOR LICENSE # 100 WELL TOTAL DEPTH 4391 FEET

OPERATOR: KCC FEE FUND #990068-001 PRODUCTION CSG: SIZE 5 1/2" @ 4384' WITH 150 SX

NAME AND 130 S MARKET RM 2078 SURFACE CASING: SIZE 8 5/8" @ 258' WITH NA SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR KCC LICENSE NUMBER 100

ADDRESS 130 S MARKET RM 2078

COMPANY TO PLUG AT: HOUR: 10:45 AM DAY: 26 MONTH: 03 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE MAIER

(COMPANY NAME) KCC (PHONE) 316-225-8888

WERE: _____

SANDED TO 3700'. RUN TUBING COULDN'T GET BELOW 1450' FELT LIKE WE WERE OUTSIDE CASING.
PULLED BACK TO 1420' AND PUMPED 60 SX CEMENT WITH 250# HULLS. PULLED TUBING TO 336' AND
WENT DOWN BACKSIDE WITH 40 SX CEMENT. MAXIMUM PRESSURE 900#. SHUT IN WITH 300#, RUN
TUBING DOWN TO 612' AND MIXED 60 SX CEMENT & 100# HULLS AND CEMENT CIRCULATED. PULLED
TUBING AND TOPPED OFF WITH 30 SX CEMENT. WAITED 1 1/2 HOURS TILL CEMENT QUIT FALLING. CEMENT
STAYED.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 26 MONTH: 03 YEAR: 1999

ACTUAL PLUGGING REPORT _____

SANDED TO 3700'. RUN TUBING COULDN'T GET BELOW 1450' FELT LIKE WE WERE OUTSIDE CASING-
PULLED BACK TO 1420' AND PUMPED 60 SX CEMENT WITH 250# HULLS. PULLED TUBING TO 336' AND
WENT DOWN BACKSIDE WITH 40 SX CEMENT. MAXIMUM PRESSURE 900#. SHUT IN WITH 300#. RUN
TUBING DOWN TO 612' AND MIXED 60 SX CEMENT & 100# HULLS AND CEMENT CIRCULATED. PULLED
TUBING AND TOPPED OFF WITH 30 SX CEMENT. WAITED 1 1/2 HOURS TILL CEMENT QUIT FALLING. CEMENT
STAYED.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael J Maier
(TECHNICIAN) FORM CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 12 12 06