

To: 1 052059
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 033-20,913 0000
App. W/2 SE SE, SEC. 18, T 34 S, R 17 W/8

TECHNICIAN'S PLUGGING REPORT

Operator License # 31898

660 feet from S section line
1200 feet from E section line

Lease Name Plumb Thicket Well # 1 18-16

Operator: Conley P. Smith Operating Co.
Name & Address 1125 17th St., Ste. 2360
Denver, CO 80202

County Comanche 210.79

Well Total Depth 6486 feet

Conductor Pipe: Size 20" feet 40

Surface Casing: Size 8 5/8" feet 705

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour 5:30 a.m. Day 4 Month 8 Year 1996

Plugging proposal received from Bill Craig

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at Arbuckle with 50 sx cement, 2nd plug at 740' with 50 sx cement,

3rd plug at 350' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour 2:15 p.m. Day 4 Month 8 Year 1996

ACTUAL PLUGGING REPORT 1st plug at 6286' with 50 sx cement,

2nd plug at 740' with 50 sx cement,

3rd plug at 350' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 08 1996

CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 8-16-96
INV. NO. 46283
8-4

Signed Richard M. Lacey (TECHNICIAN)

EFFECTIVE DATE: 7-7-96

DISTRICT # 1

SCA7... Yes... No

State of Kansas
NOTICE OF INTENTION TO DRILL 033-20,913

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 7 month 8 day 96 year
Approx. W/2 SE SE Sec 18 Twp 34 S Rg 17 XX East West

OPERATOR: License # 31898
Name: Conley P. Smith Operating Co.
Address: 1125 17th St. Suite #2360
City/State/Zip: Denver Co. 80202
Contact Person: Robert P. Vernon
Phone: (303) 296-1434

CONTRACTOR: License #: 30684
Name: Abercrombie RTD, Inc.

Well Drilled For: Well Class: Type Equipment:
XX Oil ... Enh Rec ... Infield XX Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OUVO ... Disposal XX Wildcat ... Cable
... Seismic; ... # of Holes ... Other

If OUVO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? ... yes XX no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Exp. 1/2/97

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

- 1. Notify the appropriate district office prior to sounding of well.

Pusher B.L. Leasing
SPUD DATE 7-20-96 INIT. SM
LENGTH SURFACE PLANNED 600 898'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
BATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/4 @ 725 CONDUCTOR 20" 40'
ANHYDRITE T- B- ELEVATION
RTD 6486 FORMATION _____
DRAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ 6286 Ft. W/ 50 SX
Hug./Council @ _____ Ft. W/ _____ SX
Anhydrite Base @ 740 Ft. W/ 50 SX
1/2 Base Anyh. @ 350 Ft. W/ 40 SX
1/2, 1/2 Plug @ _____ Ft. W/ _____ SX
Bottom Surface @ _____ Ft. W/ _____ SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond _____)
Hauling _____
TECHNICIAN A.L. DATE 8-2-96
TYPE OF CEMENT 60/40 per 6" size
STARTING TIME 5:30 (AM/PM) DATE 8-4-96
COMPLETION TIME 12:15 (AM/PM) DATE 8-4-96
CEMENT COMPANY Albia

660' feet from South / North line of Section
1200' feet from East / West line of Section
IS SECTION XX REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)
County: Comanche
Lease Name: PLUMB THICKET Well #: 1 18-16
Field Name: Wildcat
Is this a Prorated/Spaced Field? ... yes XX no
Target Formation(s): Mississippi/Arbuckle
Nearest lease or unit boundary: 660'
Ground Surface Elevation: 1809' feet MSL
Water well within one-quarter mile: ... yes XX no
Public water supply well within one mile: ... yes XX no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 1100' 180'
* Surface Pipe by Alternate: X 1 X 2
Length of Surface Pipe Planned to be set: 500'
Length of Conductor pipe required: N/A
Projected Total Depth: 6550'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
... well ... farm pond XX other

Will Cores Be Taken?: ... yes XX no
If yes, proposed zone: _____

* COMANCH CO. IS AN ALT 1 ONLY.
200' ALT RECEIVED
KANSAS CORPORATION COMMISSION

AUG 08 1996

CONSERVATION DIVISION
WICHITA, KS