

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR CHIEF DRILLING CO., INC. API NO. 101-20,605-0000
ADDRESS 905 Century Plaza COUNTY Lane
Wichita, Kansas 67202 FIELD _____
**CONTACT PERSON F.W. Shelton, Jr., LEASE Hutchins
PHONE 316 262-3791

PURCHASER none WELL NO. #1
ADDRESS _____ WELL LOCATION w/2 w/2 SE/4

_____ Ft. from _____ Line and
_____ Ft. from _____ Line of
the SE/4 SEC. 32 TWP. 17S RGE. 28W


DRILLING CONTRACTOR Warrior Drilling Inc.
ADDRESS 905 Century Plaza
Wichita, Kansas 67202

PLUGGING CONTRACTOR Warrior Drilling, Inc.
ADDRESS same as above

TOTAL DEPTH 4631 PBDT _____

SPUD DATE 1-11-82 DATE COMPLETED 1-21-82

ELEV: GR 2762 DF 2764 KB 2767



WELL PLAT
(Quarter) or (Full) Section - Please indicate.

KCC ☒
KGS ☒

DRILLED WITH ~~(ROTARY)~~ (ROTARY) ~~(OTHER)~~ TOOLS
Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4	8 5/8	20#	327'	common	200 sx	2%gel 3% c.c.

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Interval treated

STATE OF KANSAS
RECEIVED
CORPORATION COMMISSION
JAN 20 1982
WICHITA DIVISION
Wichita, Kansas

TEST DATE:

PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			A.P.I. Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water cu. ft.	Gas-oil ratio CFPP
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

** The person who can be reached by phone regarding any questions concerning this information.

A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum _____ Depth 600'
Estimated height of cement behind pipe _____

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST#1 4543 - 4596 30-3030-30 wk. blow died in 15 min. Rec. 5' mud IBHP: 655# FBHP: 613#, FP: 55-55			Anhydrite	2186 + 581
			Base Anhydrite	2209 + 558
			Heebner	3956 - 1189
			Lansing	3996 - 1229
			Muncie Creek	4156 - 1389
			Stark	4250 - 1483
			Hush Puckney	4287 - 1520
			BKC	4338 - 1571
			Marmaton	4351 - 1584
			Pawnee	4438 - 1671
			Lower Pawnee	4466 - 1699
			Fort Scott	4493 - 1726
			Cherokee	4517 - 1750
			Mississippi	4586 - 1819
			LTD	4624
DST#2 4577 - 4630 30-30 30-30 strong blow for 60 min. rec. 615' muddy water & mud w/few specks of oil on top IBHP: 1165# FBHP: 1125# FP: 70-204				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF KANSAS, COUNTY OF LANE SS,

F.W. SHELTON, JR. OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS VICE PRESIDENT FOR CHIEF DRILLING CO., INC. OPERATOR OF THE HUTCHINS LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. #1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 21st DAY OF January 19 82, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) F.W. SHELTON, JR.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 25th DAY OF January 19 82

Martha E. Gustin
NOTARY PUBLIC
Martha E. Gustin

MY COMMISSION EXPIRES:

