

15-015-20361-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER C 16166

LEASE NAME Drumm

WELL NUMBER 11

SPOT LOCATION SW C N/2 Lot 2

SEC. 31 TWP. 26 RGE. 8 (E) of (H) XXXX

COUNTY Butler

Date Well Completed _____

Plugging Commenced 11/4/88

Plugging Completed 11/8/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Lee Phillips Oil Co.

ADDRESS 125 N. Market, Wichita, Kansas 67202

PHONE # (316) OPERATORS LICENSE NO. 5215

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita, Kansas

Is ACO-1 filed? _____ If not, is well log attached? no

Producing formation _____ Depth to top _____ bottom T.D. 2793

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	
				8-5/8	205'	
				5-1/2	2792'	

11-15-88
NOV 15 1988

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plug back with gravel from 2700 to 2640
Mix & dump 6 sacks cement @ 2640'. Rip 5 1/2" csg. @ 1500, 1375 and 1286'.
Pulled 5 jts 5 1/2" csg. Pulled total 1286'. Put rock bridge 300' to 275'.
Bail hole dry. Had 5 yds ready mix cement put from 275' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dale Wilson- W. W. Drilling License No. 6012

Address RR #3 Box 66, El Dorado, Kansas 67042

STATE OF Kansas COUNTY OF Butler, ss.

Plugging contractor- Dale Wilson (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dale Wilson

(Address) RR #3, El Dorado, Ks 67042

SUBSCRIBED AND SWORN TO before me this 11 day of November, 19 88

Emma K. Utermochlen
NOTARY PUBLIC
State of Kansas

Emma K. Utermochlen
Notary Public

My Commission expires: MY APPT. EXPIRES 11-12-91

Form CP-4 1-84
Revised 06-83

COMPANY: LEE PHILLIPS OIL CO.
CONTRACTOR: CROWE DRILLING CO., INC.

FARM: DRUMM INSTITUTE NO. 11
LOCATION: SW/c N/2 Lot 1
Sec. 31-26-8E
Butler County, Kansas

COMMENCED: July 14, 1970
COMPLETED: July 19, 1970 (Rotary)

CASING RECORD:
205' 8 5/8" set w/150 sacks
5 1/2" set at 2793' w/80 sacks

<u>FORMATIONS</u>	<u>DEPTH</u>
Lime	470'
Lime and snale	1622'
Lime	1680'
Shale	1716'
Lime	1760'
Lansing lime	1908'
Shale	2056'
Kansas City lime	2208'
Shale	2280'
Shale and lime	2610'
Shale	2678'
Bartlesville Sand	2754'
Mississippi	2793'
TOTAL DEPTH	2793'

I hereby certify this to be a true and accurate log of the above described well as shown by the Daily Drilling Reports.

CROWE DRILLING COMPANY, INC.

L. L. L. L.

Subscribed and sworn to before me this 27th day of July, 1970.

Emyia Tomerick
Notary Public

My commission expires June 21, 1974

RECEIVED
REGISTRATION COMMISSION

REGISTRATION DIVISION
Wichita, Kansas