

15-015-20419-00-00


Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Butler County, Sec. 31 Twp. 26 Rge. 8 (E) E (W)
Location as "NE/CNW/SE" or footage from lines NE NW NE
Lease Owner Lee Phillips Oil Company
Lease Name Drumm Institute Well No. 15
Office Address 1532 KSB&T Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed April 30 1971
Application for plugging filed March 28 1974
Application for plugging approved March 29 1974
Plugging commenced April 5 1974
Plugging completed April 9 1974
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Ted E. Dewey
Producing formation Depth to top Bottom m Total Depth of Well 3871 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	193	none
				5 1/2"	3871	1846.52'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rig up and dig out cellar. Mixed and dumped 5 sacks of cement at 2757 to plug bottom.
Put a 20' rock bridge at 220' to 200' and added 3 1/2 yards of ready mix cement to plug to surface.

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1974
CONSERVATION DIVISION
Wichita, Kansas


Name of Plugging Contractor The Buckeye Corporation
Address Box 1020, El Dorado, KS 67042

STATE OF KANSAS, COUNTY OF BUTLER, ss.
Charles V. Cross (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 1020, El Dorado, Ks 67042
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April 1974

My commission expires



Notary Public.

COMPANY: LEE PHILLIPS OIL CO.
CONTRACTOR: CROWE DRILLING CO., INC.

FARM: DRUM INSTITUTE NO. 15
LOCATION: NE/4 NW/4 NE/4
Sec. 31-26-8E
Butler County, Kansas

COMMENCED: April 19, 1971
COMPLETED: April 30, 1971 (Rotary)

CASING RECORD:
193' of 8 5/8" set w/130 sacks
5 1/8" set at 3871' w/225 sacks

<u>FORMATIONS</u>	<u>DEPTH</u>
Surface Hole	800'
Lime and shale	1490'
Shale and sand	1729'
Lansing Lime	1875'
Shale	2047'
Kansas City Lime	2217'
Shale	2280'
Shale and lime	2685'
Sand, Bartlesville	2755'
Bartlesville Shale	2781'
Mississippi Lime	3150'
Kinderhook Shale	3184'
Viola	3214'
Simpson Shale	3238'
Lime, Arbuckle	3858'
Granite Wash	3871'
TOTAL DEPTH	3871'

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1974
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify this to be a true and accurate log of the above described well as shown by the Daily Drilling Reports.

CROWE DRILLING COMPANY, INC.

[Signature]

Subscribed and sworn to before me this 3rd day of May, 1971.

[Signature]
Notary Public

My commission expires June 21, 1974