

15-015-20509-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Butler SEC. 31 TWP. 26 RGE. 8E E/W
Location as in quarters or footage from lines:
NE/c S/2 Lot 18

Lease Owner Lee Phillips Oil Company
Lease Name Drumm Inst. #17 Well No. _____
Office Address 125 N. Market Suite 1532 Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 10-19-82
Plugging completed 10-21-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson
Producing formation _____ Depth to top _____ bottom T.D. 2815'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	208'	none
				5-1/2"	2812'	1494'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bridge @2220', set 7 sacks cement, shot casing @1504', pulled a total of 47 joints of 5-1/2" casing. Set rock-bridge @300' and ran 4 yards of ready-mix cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1982

My Commission expires: _____



RECEIVED
Notary Public.
STATE CORPORATION COMMISSION

OCT 28 1982

CONSERVATION DIVISION
Wichita, Kansas

COMPANY: LEE PHILLIPS OIL CO.
CONTRACTOR: GROVE DRILLING CO., INC.

FARM: DEWEEB INST. NO. 17
LOCATION: NE/4 S/2 Lot 18
Sec. 31-26-2E
Butler County, Kansas

COMMENCED: May 7, 1972
COMPLETED: May 12, 1972 (Rotary)

CASING RECORD:
208' of 8 5/8" set w/75 sacks
5 1/2" set at 2812' w/80 sacks

<u>FORMATIONS</u>	<u>DEPTH</u>	
Line and shale	1270'	Perforations:
Shale and shells	1410'	2710-34 Set plug @ 2700.
Shale and sandy lime	1742'	2640-70
Lansing lime	1945'	Workover:
Shale	2073'	Drove plug 2700 to 2760.
Kansas City Lime	2075'	Set plug @ 2690 for input
Shale	2238'	well.
Shale and lime	2634'	
Sand	2672'	
Shale	2707'	
Sand	2710'	
Shale and sand	2797'	
Mississippi Lime	2815'	
Total Depth	2815'	

I hereby certify this to be a true and accurate log of the above described well as shown by the Daily Drilling Reports.

GROVE DRILLING COMPANY, INC.

L. L. Groves

Subscribed and sworn to before me this 15th day of May, 1972.

Emma Dominick
Notary Public

My commission expires June 21, 1974