


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Butler County, Sec. 31 Twp. 26 Rge. 8E (E) (W)  
Location as "NE/CNW/SE/SW" or footage from lines SE 1/4 Lot 1  
Lease Owner Frank Black  
Lease Name Drumm #3 Well No.  
Office Address McPherson, Kansas 67460  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19\_\_\_\_  
Application for plugging filed 19\_\_\_\_  
Application for plugging approved 19\_\_\_\_  
Plugging commenced 12-18-75 19\_\_\_\_  
Plugging completed 12-22-75 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.  
If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Dewey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3725 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8  | 150    | none       |
|           |         |      |    | 5 1/2" | 3290   | 1432       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, ran sand to 2650' and dumped 5 sacks cement.  
Loaded hole, shot pipe at 2305', 2123', 2010', 1920', 1810',  
1700', 1620', 1511', 1423', pulled 47 joints. Set rock bridge  
at 180' and dumped 3 yards ready mix.

PLUGGING COMPLETE

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 29 1975  
12-29-75  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KELSO CASING PULLING  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. Darrell Kelso*  
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1975

My commission expires

NOTARY PUBLIC  
MARGARET MELCHER  
Rice County, Ks.  
My Comm. Exp. Feb. 15, 1979

*Margaret Melcher*  
Notary Public.

NOTARY PUBLIC  
MARGARET MELCHER  
Rice County, Ks.  
My Comm. Exp. Feb. 15, 1979

COMPANY: LEE PHILLIPS OIL CO.  
CONTRACTOR: GROWE DRILLING CO., INC.

FAIR: ANDREW DUNHAM TRST. NO. 3  
LOCATION: SE/c Lot 1  
Sec. 31-269-8E  
Butler County, Kansas

COMMENCED: July 3, 1969  
COMPLETED: July 13, 1969 (Rotary)

CASING RECORD:  
150 ft. 8 5/8" w/75 sacks  
5 1/2" set at 3290' w/150 sacks

| <u>FORMATIONS</u>     | <u>DEPTH</u> |               |  |
|-----------------------|--------------|---------------|--|
| Surface hole and lime | 159'         | Brown lime    | 1627 - 83                              |
| Flint and lime        | 215'         | Lans.         | 1705 - 161                             |
| Lime                  | 352'         | K.C.          | 2053 - 509                             |
| Shale and lime        | 1504'        | BKC           | 2222 - 678                             |
| Sand and shale        | 1620'        | Oawbee        | 2366 - 822                             |
| Lime and shale        | 1722'        | Ft. Scott     | 2436 - 892                             |
| Lansing lime          | 2080'        | Cherokee      | 2482 - 938                             |
| Kansas City lime      | 2222'        | B'ville       | 2680 - 1136                            |
| Shale                 | 2384'        | Base B.       | 2752 - 1208                            |
| Shale and lime        | 2737'        | Miss.         | 2792 - 1248                            |
| Sand                  | 2751'        | Kinderhook    | 3139 - 1595                            |
| Shale and lime        | 2792'        | Viola         | 3191 - 1647                            |
| Mississippi lime      | 3086'        | Simpson       | 3196 - 1652                            |
| Lime                  | 3155'        | Arbuckle      | 3200 - 1656                            |
| Shale                 | 3199'        | T.D.          | 3725.                                  |
| Lime                  | 3725'        |               |  |
| TOTAL DEPTH:          | 3725'        | SWD well      |  |
|                       |              | Perf. B'ville | 2683-87 w/16 sh.<br>2698-2702 w/16 sh. |

I hereby certify this to be a true and accurate log of the above described well as shown by the Daily Drilling Reports.

GROWE DRILLING COMPANY, INC.

*J. Deloraine*

Subscribed and sworn to before me this 13th day of July, 1969.

*Emory Dominick*  
Rotary Public

My commission expires June 21, 1970