


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Butler County, Sec. 31 Twp. 26 Rge. 8E (E) (W)
Location as "NE/CNWKSWK" or footage from lines NW 1/4 S/2 Lot 1
Lease Owner Frank Black
Lease Name Drumm #6 Well No.
Office Address McPherson, Kansas 67460
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 12/22/75 19____
Plugging completed 12/29/75 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dewey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2799 feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD			
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT	
				8-5/8	169	none	
				5 1/2"	2798	1505'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, ran sand to 2650' and dumped 5 sacks cement. Loaded hole, shot pipe at 1770', 1680', 1589', 1490', pulled 47 joints. Set rock bridge at 170' and ran 24 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ~~XXXXX~~ KELSEY CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of December 19 75

My commission expires _____
NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

COMPANY: BOB HILLIERS OIL CO.
OPERATOR: CROWE DRILLING CO., INC.

FARM: DRUM NO. 6
LOCATION: 1/4/3 3/2 Lot 1
Sec. 31-26-23
Butler County, Kansas

COMPLETED: February 5, 1970
COMPLETED: February 9, 1970 (Rotary)

CASING RECORD:
169 feet of 8 5/8" set w/175 sacks
5 1/2" set at 2798' w/80 sacks

FORMATION

DEPTH

Surface Hole 169'
Lime and shale 490'
Shale 705'
Shale and lime 950'
Lime 995'
Shale and lime 1105'
Shale and shells 1360'
Shale 1495'
Sand 1580'
Shale and lime 1710'
Lime 1830'
Shale and lime 2050'
Kansas City Lime 2050'
Lime 2210'
Shale and lime 2734'
Sand 2743'
Shale 2749'
Sand and shale 2773'
Mississippi lime 2799'
TOTAL DEPTH 2799'

Perf. 2681-84; 2686-2690;
2707-2713.

RECEIVED
STATE CORPORATION COMMISSION

DEC 1 1970

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify this to be a true and accurate log of the above described well as shown by the Daily Drilling Reports.

CROWE DRILLING COMPANY, INC.

H. Brown

Subscribed and sworn to before me this 11th day of February, 1970.

Emya Dominick
Notary Public

My commission expires 6-31-70