

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Rohrer
 WELL NUMBER 1
 _____ Ft. from S Section Line
 _____ Ft. from E Section Line
 SEC. 22 TWP. 33 RGE. 3W (E) or (W)
 COUNTY Sumner
 Date Well Completed _____
 Plugging Commenced 7-25-94
 Plugging Completed 7-27-94

LEASE OPERATOR Dean Allison Oil Company
 ADDRESS 212 N. Market, 507 Landmark Sq., Wichita, KS 67202
 PHONE# (316) 267-2672 OPERATORS LICENSE NO. 6765

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
 by Jerry Clark (KCC District Agent's Name).

Is ACQ-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4481'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	253'	none
				4 1/2	3596'	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Sanded off bottom @ 3450' & ran 4 sks cement. Shot @ 3000 & 2700, pipe came loose. Pulled up to 650' & pumped 35 sks cement. Pulled up to 350' & circulated 130 sks to surface. Pulled rest of pipe. Tore down & tallied pipe. 60/4- poz 4% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050
 Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEELS: Dean Allison Oil Company
 STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 94

Isma Herzberg
 Notary Public

My Commission Expires: _____



4765
15-191-20630-0000

**GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG**

Rohrer #1
150' W of SE SE SE Sec 22-33S-3W
Summer County Kansas

Commenced: 11-16-76

Completed: 11-30-76

OPERATOR: ALLISON OIL CO.

Depth		Formation	Remarks
From	to		
0	256	Redbed	Ran 6 jts of 8 5/8" csg set @ 253' Cemented w/ 225 sks - 2% Gel - 3% CC PD @ 8:45 p.m. 11-16-76
256	650	Shale	
650	1192	Shale-Shells	Ran 86 jts of New 4 1/2" csg set @ 3596' Cemented w/100 sks 50/50 posmix 18% Salt - 3/4 of 1% CFR-2 PD @ 2:15 a.m. 11-30-76 PERF. 3504' TO 09' 4 PER FT. D P'S
1192	1360	Lime-Shale	
1360	1630	Shale	
1630	1865	Shale-Lime	
1865	2020	Lime-Shale	
2020	2200	Shale	
2200	2600	Lime-Shale	
2600	2810	Shale-Lime	
2810	3035	Lime-Shale	
3035	3115	Sand	
3115	3145	Shale-Lime	
3145	3275	Shale-Sandy Lime	
3275	3820	Lime	
3820	3885	Lime-Shale	
3885	4430	Lime	
4430	4475	Shale	
4475	4481	Lime	
	4481 - TD		

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

RECEIVED
STATE CORPORATION COMMISSION

GABBERT-JONES, INC.

JUL 05 1994

James S. Sutton
JAMES S. SUTTON II

CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 6th day of December, 1976.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979..

