

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 31 Twp. 33S Rge. (E) 6 (W)

Location as "NE/CNW&SW&" or footage from lines. C-NE/4-NW/4
Lease Owner Amerada Petroleum Corporation
Lease Name William Steward Well No. 1
Office Address Box 197, Great Bend, Kansas-67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-29- 19 65
Application for plugging filed 12-29- 19 65
Application for plugging approved 1-4 19 66
Plugging commenced 3:00 p.m. 12-29- 19 65
Plugging completed 6:00 p.m. 12-29- 19 65
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation None Depth to top - Bottom - Total Depth of Well 5010 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	247'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with Heavy Mud from 5010' to 250'
Spotted Cement Plug from 250' to 150' With 35 Sacks Cement by Halliburton
Filled Hole with Heavy Mud from 150' to 40'
Spotted Cement Plug from 40' to top of Cellar with 10 Sacks Cement by Halliburton
Filled rat hole with 5 Sacks Cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1966
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling Company Inc.
Address 1815 Wichita Plaza, Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
C.E. Richardson (employee of owner) ~~operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.E. Richardson
C.E. Richardson
Box 197, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of January 19 66

My commission expires November 21, 1969

Charles W. Anderson
Charles W. Anderson Notary Public.

DRILLER'S LOG

COMPANY: Amerada Petroleum Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: STEWARD #1
 LOCATION: C NE NW Sec. 31-33S-6W
 HARPER COUNTY, KANSAS
 COMMENCED: 12-10-65
 COMPLETED: 12-29-65

0	258	Redbed
258	548	Shale
548	1200	Shale, Shells
1200	1330	Shale, Lime
1330	2155	Lime, Shale
2155	2425	Shale
2425	3240	Shale, Lime Streaks
3240	3472	Lime, Shale
3472	3650	Shale, Lime
3650	3720	Shale, Sand
3720	3767	Shale, Lime
3767	3880	Shale, Sand
3880	4068	Lime, Shale
4068	4188	Lime
4188	4446	Lime, Shale
4446	4510	Shale, Lime
4510	4545	Lime
4545	4630	Shale, Lime
4630	4675	Lime, Shale
4675	4745	Lime
4745	4915	Lime, Shale
4915	4955	Lime, Shale, Chert
4955	4958	Lime, Shale
4958	4965	Sand
4965	5010	Simpson Sand
	<u>5010</u>	<u>RTD - D. & A.</u>

RECORDED
 STATE COMMISSIONER OF REVENUE
 JAN 10 1966
 CHARLES W. WATSON, Director
 OFFICE OF REVENUE, KANSAS

Set 8 5/8" new 24# casing @ 256' with 200 sacks Common, 2% cc in last 100 sacks

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Steward #1 well, located C NE NW Section 31, Township 33 South, Range 6 West, Harper County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 31st day of December, 1965.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
 April 1, 1967