

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-063-21,329-0000

LEASE NAME Lundgren

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 31 TWP. 14 RGE. 29 (W) or (W)

COUNTY Gove

Date Well Completed 5-7-90

Plugging Commenced 5-7-90

Plugging Completed 5-7-90

LEASE OPERATOR Viking Resources, Inc.

ADDRESS 105 S. Broadway, Suite 1040, Wichita, KS 67202

PHONE# (316) 241-4640 OPERATORS LICENSE NO. 5011

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-7-90 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4290'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		212'	0'	8-5/8"	212'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Plugged hole with 200 sacks 60/40 pozmix, 6% gel, 2% cc as follows: 25 sx @ 2040', 100 sx @ 1050', 40 sx @ 260', 10 sx @ 40' to surface, 15 sx R.H., 10 sx M.H. P.D. @ 11:45 p.m. 5-7-90.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P.O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Viking Resources

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

James B. Deulin (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) James B. Deulin

(Address) 105 S. BROADWAY, SUITE 1040

WICHITA, KS 67202-4224

SUBSCRIBED AND SWORN TO before me this 25th day of May, 1990

Paula R. Dunagan
Notary Public

Expires: March 2, 1993



RECEIVED

Form CP-4
Revised 05-88

MAR 12 2013
3-12-13
KCC WICHITA

MALLARD JV, INC.
P.O. BOX 1009
McPHERSON, KS 67460

DRILLERS' LOG

OPERATOR: Viking Resources, Inc.
105 S. Broadway, Suite 1040
Wichita, KS 67202

WELL: Lundgren #1

API#: 15-063-21,329-0000

COMMENCED: April 30, 1990

LOCATION: SW SW NE

COMPLETED: May 7, 1990

2970 Ft. FSL, 2310 Ft. FEL

TOTAL DEPTH: 4290 Ft.

SEC. 31 TWP. 14 S RGE. 29 W

ELEVATION: 2621 Ft. G.L.

COUNTY: Gove

2629 Ft. K.B.

D & A - Mississippi Formation

REMARKS:

Cut 12 1/2" hole to 215' and ran 5 joints 8-5/8" x 20# x 202.4' surface casing. Set at 212' and cemented with 140 sacks 60/40 Pozmix, 2% gel, 3% cc. Cement did circulate. P.D. @ 3:05 a.m. 5-1-90.

Ran 3 DSTs.

Plugged hole with 200 sacks 60/40 Pozmix, 6% gel, 2% cc as follows:

- 25 sx @ 2040'
- 100 sx @ 1050'
- 40 sx @ 260'
- 10 sx @ 40' to surface
- 15 sx R.H., 10 sx M.H.
- P.D. @ 11:45 p.m. 5-7-90.

STATE OF KANSAS)
COUNTY OF MCPHERSON) SS:

I, Dick Hess of MALLARD JV, INC. hereby certify that this is a true and correct copy of the log of the Lundgren #1 well as reflected by the files of Mallard JV, Inc.

Dick Hess
Dick Hess

Subscribed and sworn to before me this 15th day of May, 1990.



Bryan K. Hess
NOTARY PUBLIC

RECEIVED
MAR 12 2013

KCC WICHITA